

15-163-03695-00-01

4-27

4-041461

E-13,043

API number: 15- - 4-16-45

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

S2 SW SW /4 SEC. 27 , 08 S, 16 W  
330 feet from S section line  
4620 feet from E section line

Operator license# 30606

Lease North Laton Unit well # 3-1

Operator: Murfin Drilling Co., Inc.

County Rooks

Address: 205 N. Water  
Suite 300  
Wichita, Kansas 67202

Well total depth 3300 feet, <sup>07.25</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 1248 feet  
w/350 sx.

Aband. oil well     , Gas well     , Input well X, SWD     , D & A     

Plugging contractor: Halliburton Cementing License#     

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:30A.M. Day: 27 Month: April Year: 93

Plugging proposal received from: John Gertschner

Company: Murfin Drilling Co., Inc. Phone:     

Were: 5 1/2" casing set @ 3119' w/100 sx. cement. Perf. @ 3269'-3299'.  
Perfs/D.V.: Salt @ 2000'. Anhy. @ 1240'. Dakota @ 725'. W.L.M. 3150'.  
2 7/8" tubing cemented @ 3348' w/50 sx. cement. Pulled 3051' of 1"  
fiberglass lined tubing. Pressured-up 2 1/2" tubing to 500# to test.  
Ordered 375 sxs. 60/40 pozmix - 8% gel. with 1/4# F.C. plus 100# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: P.M., Day: 27, Month: April, Year: 93

Actual plugging report: Perf. 2 1/2" - 5 1/2" casing @ 3100' & 2050'.  
Hooked-up to 2 1/2" tubing pumped in 145 sxs. cement to circulate  
annulus of 2 1/2" - 5 1/2" casing. Shut-in same, squeezed to 700#.  
Shot hole in casing @ 1240', squeezed 200 sxs. cement in 5 1/2" - 10 3/4"  
annulus with good circulation - locked up. P.S.I. to 1000#. Est.  
T.O.C. 269'. Shot hole in casing @ 200' - circulated 30 sx. cement to  
surface.

Remarks:

Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES  , CALC  , NO  Dakota plug: YES  , NO   
Plugged through TUBING  , CASING  . Elevation: 1961 GL

I did  / did not  observe the plugging.

**INVOICED**

DATE 6-11-93

INV. NO. 37876

Dennis L. Hamel

(agent) CONSERVATION DIVISION  
Wichita, Kansas

Form CP-2/3

6/9/93

RECEIVED  
STATE CORPORATION COMMISSION

JUN 9 1993