

~~15-163-30020-00-00~~ 7 31 15-163-02979-00-01 <sup>(SIC)</sup>

6 041201

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- D-9359 NA  
SW SE NE, SEC. 18, T 8 S, R 16 W7E<sup>x</sup>

2970 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8735

Lease Name N. Chesney Well # D-1

Operator: S and M Oil Co.

County Rooks 108.12

Name & Address 205 N. Jefferson

Well Total Depth 3327 PB 1180 feet

Plainville, Ks. 67663

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1130

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor allied Cement License Number \_\_\_\_\_

Address Russell, Ks.

Company to plug at: Hour: 8:00AM Day: 31 Month: July Year: 19 90

Plugging proposal received from Steve Crawford

(company name) S and M Oil (phone) \_\_\_\_\_

were: 5 1/2 set at 3175 w/cement na: Perf at 3054 - 3068.

Plugged back to 1180 (5 1/2 casing pulled prior years and converted to shallow SWD.

\*Plug back cement records not available)

Ordered 250 sks 65/35 poz 8% gel w/1/4 lb f.c. plus 3 sks hulls in cement.

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part xx None \_\_\_\_\_

Operations Completed: Hour: 10:30AM Day: 31 Month: July Year: 19 90

ACTUAL PLUGGING REPORT R.I.H. w/tubing to 1180; pumped 200 sks

cement to circulate at surface; P.O.O. H w/tubing. Hoooked up ~~1000~~ 1000 s.p. and

sq 50 sks cement. Max psi 500 lbs. S.I. 300 lbs. STATE CORPORATION COMMISSION

Aug 24 1990 824-90

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE: 8-28-90

INV. NO. 28142

*J.S.*

Signed Dennis L. Hamel  
(TECHNICIAN)  
Dennis L. Hamel