

8-20 15-163-03901-00-00

12-1-61

To: **6 041211**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
NE SW SE, SEC. 18, T 8 S, R 16 W7E

TECHNICIAN'S PLUGGING REPORT

Operator License # 8735
Operator: S and M Oil Co.
Name & Address 205 N. Jefferson
Plainville, Ks. 67663

990 feet from S section line
1650 feet from E section line

Lease Name Chesney Well # A - 3
County Rooks 104.27

Well Total Depth 3207 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 250 w/cement NA

Abandoned Oil Well xx Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address Russell, Ks.

Company to plug at: Hour: 8 Day: Month: Year: 19

Plugging proposal received from Steve Crawford

(company name) S and M (phone)

were: 4 1/2 casing set at 3205 w/NA sks cement: perfs at 2728 to 3168: Perf anhy 1175; perf base dakota at 675. Dakota sq info. N.A.; Tubing in hole - rods and pulled pump out; Ordered 300 sks 65/35 poz 10% gel w/1/4 lb f.c. plus 5 sks hulls.

RECEIVED
STATE CORPORATION COMMISSION

SEP 1 11 1990 9-10-90

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part None

Operations Completed: Hour: 12:45PM Day: 20 Month: August Year: 1990

ACTUAL PLUGGING REPORT R.I.H. w/tubing gun shot casing and tubing

at 1175: Hooked up to 2 1/2 tubing and pumped 25 sks cement w/1/4 lb. f.c. plus 75 sks cement w/1/4 f.c. plus 200 lbs. hulls mixed in cement. Pressured up to 750 lbs. psi: R.I.H. and shoot casing at 675: P.S.I. at 300 - 325 lb.: Pumped in 75 sks cement w/100 lbs. hulls, psi to 750 lbs.; Opened 4 1/2 lbs. casing and cir cement to surf from 675 w/25 sks cement; Shut in casing pumped add 70 sks cement in tubing - casing to a psi of 800 lbs.

Remarks: Shut in same. (30 min). Released pressure. R.I.H. and perf tubing, casing at 200 ft. Pumped in 30 sks cement to cir cement in annulus of 4 1/2 lb. casing or s.p.

(If additional description is necessary, use BACK of this form.)

INVOICED
(If cement circ all casing from 200 to surf. observe this plugging.)

DATE: SEP 18 1990
INV. NO. 29355

Sub S.

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis Hamel