

To: **6 041183**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

6-19  
15-163-81122-00-01  
API NUMBER 15-  
A-20, 801  
SW NW SE, SEC. 18, T 8, R 16 W&E

TECHNICIAN'S PLUGGING REPORT

Operator License # 8735  
Operator: S and M Oil CO.  
Name & Address 205 N. Jefferson  
Plainville, Ks. 67663

1650 feet from S section line  
2310 feet from E section line  
Lease Name Chesney Well # A-2  
County Rooks 104.65  
Well Total Depth 3220 feet  
Conductor Pipe: Size        feet         
Surface Casing: Size 8 5/8 feet 250' w/150

Abandoned Oil Well        Gas Well        Input Well X SWD Well X D&A       

Other well as hereinafter indicated       

Plugging Contractor Allied Cement Co. License Number         
Address Russell, Ks.

Company to plug at: Hour: 1:00PM Day: 19 Month: June Year: 19 90

Plugging proposal received from Steve Crawford  
(company name) S and M Oil (phone)       

were: 4 1/2 casing set at 3220 w/cement. NA perf at 2746 - 3166.  
Perf at 1180 and base dakota 650. (three holes each). Sq casing 350 to surf.  
Ordered 50 sks common w/1/4 lb f.c. plus 250 sks 65/35 poz 8% gel w/1/4 lb. f.c.

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part        None       

Operations Completed: Hour: 4:00 PM Day: 19 Month: June Year: 19 90

ACTUAL PLUGGING REPORT R.T.H. w/tubing to 1245; spot 50 sks common w/  
1/4 lb f.c. PULL tubing to 845; spot 50 sks 65/35 poz 8% gel w/1/4 lb f.c. PHIL tubing to 445;  
circ cement to surf. w/100 sks w/1/4 lb f.c. and 100 lbs hulls. Pulled tubing;  
hooked up to 4 1/2 and sq 25 sks 65/35 poz 8% gel and 1 sk hulls: Max 600 lbs. s.i. 300 lbs.

Remarks: (If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 7-17-90  
INV. NO. 28618

Signed Dennis L. Hamel  
Dennis Hamel (TECHNICIAN)

JUL 12 1990  
CONSERVATION DIVISION  
Wichita, Kansas