

6 010729

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-23,111-00-00

SW SW, SEC. 15, T 8 S, R 16 W/E
990 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5141

Lease Name Conn Well # 1

Operator: Zenith Drilling
Name & Address: 100 H. Broadway
Wichita, Ks.

County Rooks 115.86

Well Total Depth 3565 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor Red Tiger License Number 5302

Address Wichita, Ks.

Company to plug at: Hour: Day: 7 Month: Oct Year: 19 90

Plugging proposal received from Ken Lyle

(company name) Red Tiger (phone)

were: Order 215 sks cement 60/40 poz 6% gel and 2 sks f.c. Heavy mud between all plugs.

Pump cement down drill pipe.

Elevation 1959 Anhy 1293 - 1322 Arb. 3505

top Dakota 1450

Plugging Proposal Received by D.F.B. (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 3:00 PM Day: 7 Month: Oct Year: 19 90

ACTUAL PLUGGING REPORT
25 sks at 3505
25 sks at 1320
100 sks at 800
40 sks at 300
10 sks at 40
15 sks in rathole

Remarks: Halliburton Cementing Co.

Additional description is necessary, use BACK of this form.)

I (skc / did not) observe this plugging.

DATE 10-19-90

REV. NO. 29679

[Signature]

Signed Dale F. Balthazor (TECHNICIAN)

Dale F. Balthazor

RECEIVED
STATE CORPORATION COMMISSION
10-19-90
OCT 15 1990

CONSERVATION DIVISION
Wichita, Kansas