

10-3-87

To: 6 070603
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-22,946 -00-00

SE SE SE, SEC. 1, T 8 S, R 17 W/E

330 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3446

Lease Name Schultz Well # 1-1

Operator: Columbia Gas Div. Co.

County Rooks 113.10

Name & Address: Box 1350

Well Total Depth 3480 feet

Houston, Texas 77251-1350

Conductor Pipe: Size 0 feet

J. C. Braswell, Jr.

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Inc. License Number Tag 76

Address 1720 Kansas State Bank Bldg. Wichita, Kansas 67202

Company to plug at: Hour: 11:00 AM Day: 3 Month: October Year: 19 87

Plugging proposal received from Pat Waggoner

(company name) Red Tiger Drilling Inc. (phone) 316-263-1201

were: 8 5/8" 261' S. P. cwc w/160 sks 60/40 Pozmix 2% Gel 3% Ca Cl. By B. J. Titan.

Elevation 1943' Anhydrite 1231'. No circulation problems. Mud 9.8 weight, vis. 46, water

loss 6. (L. C. M. 5 lbs.) Proposal 225 sks 60/40 Pozmix 6% Gel 3% Ca Cl and 1 sk Celloflake.

Spot with drill stem. Recondition hole, heavy mud between all plugs. 25 sks at 3390' 25 sk

at 1250' 100 sks w/1 Flocele at 760' 50 sks at 300' 10 sks at 40'. 15 rat hole (circulate)

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:00 AM Day: 3 Month: October Year: 19 87

ACTUAL PLUGGING REPORT Ordered 225 sks 60/40 Pozmix 6% Gel 3% Ca Cl and 8 5/8" plug.

Spotted with drill stem, recondition hole, heavy mud between all plugs. 1st plug 25 sks

at 3390'. 2nd plug at 1250' w/25 sks. 3rd plug 100 sks w/1 sk Flocele at 760'.

4th plug 50 sks at 300'. 5th plug Hulls and plug at 40' w/10 sks cement. 15 sks rat hole

(cir) Cemented by B. J. Titan.

Remarks: (If additional description is necessary, use BACK of this form)

did not observe this plugging.

OCT 23 1987
10-23-87
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

Signed Marion J. Schmidt (TECHNICIAN)
Marion J. Schmidt

DATE 10-26-87

INV. NO. 18652

10-03