

5-19

4-061077

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-141-20,336 00-00  
SE SE NE /4 SEC. 25, 08 S, 12 W  
2970 feet from S section line  
330 feet from E section line

Operator license# 3956

Lease Louise Bader Well # 1

Operator: Brungardt Oil & Leasing

County: Osborne 105.63

Address: Box 871  
Russell, Kansas 67665

Well total depth 3250 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 206 feet

Aband. oil well\_\_\_, Gas well\_\_\_, Input well\_\_\_, SWD\_\_\_, D & A X

Plugging contractor: Shields Oil Producers License# 5184

Address: Russell, Kansas 67665

Company to plug at: Hour: 2:00 A.M. Day: 19 Month: May Year: 1997

Plugging proposal received from: \_\_\_\_\_

Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Were: Order 150 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 4:30 A.M., Day: 19, Month: May, Year: 1997

Actual plugging report: \_\_\_\_\_

1st. Plug at 810' w/25 sxs. Anhydrite 790' - 823'.

2nd. Plug at 635' w/90 sxs. Dakota 331' - 631'.

3rd. Plug at 40' w/10 sxs. Surface pipe 206'.

15 sxs in rathole.

10 sxs in mousehole

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_

Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO X Dakota plug: YES X, NO \_\_\_\_\_

Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_. Elevation: 1681 GL

I did[ ] / did not[ X ] observe the plugging.

DATE JUN 09 1997

INV. NO. 48286

Herb Deines  
(agent)  
Form CP-2/3

RECEIVED  
KANSAS CORP COM  
JUN 10 1997  
64-97

INVOICED