

6-4

4-061086

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-141-20,337-0000

NW NW SE /4 SEC. 27, 08 S, 12 W  
2300 feet from S section line  
2300 feet from E section line

Operator license# 9860

Lease: Schweitzer Well # 1

Operator: Castle Resources, Inc.

County: Osborne

97.40

Address: 1200 E. 27th St. - #C  
Hays, Kansas 67601

Well total depth 2997 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 203 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Co Tools License# -

Address:

Company to plug at: Hour: 2:00 P.M. Day: 4 Month: June Year: 1997

Plugging proposal received from: Jerry Green

Company: Castle Resources, Inc. Phone: 913-625-5155

Were: Ran casing to test new well. Tested non-commercial. Emergency permission to plug hole with rig over hole. Plug while pulling casing. Order 150 sxs 60/40 posmix - 6% gel and hulls.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 7:00 P.M., Day: 4, Month: June, Year: 1997

Actual plugging report: 8 5/8" to 203' w/135 sxs. 4 1/2" to 3026' w/100 sxs. Perfs at 2918' - 2920'. Mixed 25 sxs cement with hulls and displaced to 2600'. Cut casing at 2502' and pulled to 850' and pumped 40 sxs with 100# hulls. Pulled to 550' and pumped 30 sxs with 100# hulls. Pulled casing to 150' and circulated with 30 sxs. Pulled casing and topped with 5 sxs cement.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES X, CALC, NO  
Plugged through TUBING X, CASING. Elevation: 1647 GL  
Anhy.plug: YES X NO  
Dakota plug: YES X, NO

I did [ ] and did not [ X ] observe the plugging.

INVOICED  
DATE 7-30-97  
INV. NO. 48688