

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION
Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: April 2006 (Date)
by: David Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Topeka Depth to Top: 2750 Bottom: 2764 T.D. _____
Toronto Depth to Top: 2784 Bottom: 2792 T.D. _____
LKC Depth to Top: 2816 Bottom: 3039 T.D. 3125

API Number: 15-167-36600-00-02
Lease Name: Dodge
Well Number: #1
Spot Location (QQQQ): _____ - SE - SW - SW
330' Feet from North / South Section Line
990' Feet from East / West Section Line
Sec. 32 Twp. 11S S. R. 15W East West
County: Russell
Date Well Completed: November 2005
Plugging Commenced: 6/8/06
Plugging Completed: 6/12/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Prod				6-5/8	2525' 2585'	-----
Prod				5-1/2	2847' 2800'	-----
Prod				4-1/2	2696-3065	-----
KCC 7/21/06 PCT Per CP 2/3						


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

MIRU to Plug and Abandon. Perf'd 2 SPF at 1550'; 920' and 470'. SDON. TIH w/2-7/8 tbg (workstring) to 2600'. RU Allied and spotted 40 sx 60/40 poz cement w/10% gel with 15 sx gel on top. Pulled tbg to 1590'. Mixed 20 sx cement and pump truck broke down. Balanced cement plug and TOH w/tbg. Waiting on replacement truck. TIH w/tbg to 1630' Pumped 135 sx cement and circulated to surface. TOH w/tbg. Filled csg w/90 sx. cement at 440#. SIP - 250#. Press 6-5/8" to 600# - OK. Appr by Jay Pfeifer @ KCC

Name of Plugging Contractor: Allied Cementing Co., Inc. Smoky Hills Well Service License #: 3245
Address: P.O. Box 31, Russell, KS 67665-0031
Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Sedgwick, ss. Pat Canaday
Pat Canaday (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 13th day of July
Michelle D. Henning My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten signature]

[Handwritten initials]

