

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

JUL 17 2006

Form CP-4

September 2003

Type or Print on this Form

Form must be Signed

All blanks must be Filled

KCC WICHITA

159-06354-00-00

Lease Operator: Scheck Oil Operation

Address: 225 N. Main Russell, KS 67665

Phone: 785 483-1292 Operator License #: 9292

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Virgil Cothier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____	Depth to Top: _____	Bottom: _____	T.D. _____
_____	Depth to Top: _____	Bottom: _____	T.D. _____
_____	Depth to Top: _____	Bottom: _____	T.D. _____

API Number: 15-00-279-4

Lease Name: J.R. Lansing

Well Number: A-11

Spot Location (QQQ): NW/4 NE/4 SW/4
2310 Feet from _____ North / South Section Line

3630 Feet from East / West Section Line

Sec. 25 Twp. 18 S. R. 8 East West

County: Rice

Date Well Completed: _____

Plugging Commenced: 7-7-06

Plugging Completed: 7-11-06

KCC-PKT
7-21-06 Per
Flgs
CPSD

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	<u>Surf Prod</u>			<u>8 5/8</u>	<u>300'</u>	<u>None</u>
				<u>5 1/2</u>	<u>3162'</u>	<u>None</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Sanded bottom to 2800' w/ 5sx. cement. Perf well at 1050', 700', & 350'.

Mixed 35sx. cement at 1050', pulled to 700', mixed 35sx., pulled 350', mixed 250sx. cement. Cement didn't circulate, top of cement at 340', ran tubing to 340', mixed up 5sx. gel & 140sx. cement. Cement circulated to surface. Topped with 20sx. cement. 60/40poz. 4%gel

Name of Plugging Contractor: Mike's Testing & Salvage License #: 31529

Address: Box 467 Chase, KS 67524

Name of Party Responsible for Plugging Fees: Scheck Oil

State of Kansas County, Rice ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) Box 467 Chase, KS 67524

SUBSCRIBED and SWORN TO before me this 14th day of July, 20 06

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PCT