

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Meritage KCM Exploration, LLC
Address: 1050 17th Street Suite 975 Denver, Colorado 80265
Phone: (303) 534-9513 Operator License #: 33138
Type of Well: SW Disposal Docket #: D-28123
The plugging proposal was approved on: April 13, 2006
by: David P. Williams
Is ACO-1 filed? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Open hole Depth to Top: 1451' Bottom: 1805' T.D. 1805'

API Number: 15-003-24222-00-00
Lease Name: Garrison
Well Number: 26-13 SWD
Spot Location (QQQQ): - NW - NW - SW
2310 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 26 Twp. 19 S. R. 19 East West
County: Anderson
Date Well Completed: 1/15/2003
Plugging Commenced: 6/14/06
Plugging Completed: 6/15/06

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Surface casing and Prod.


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Run tbg down well to 1396'. Mix & pump down tbg 160 sks 60/40 Poz mix w/4% gel & 1/4# Flo seal w/120# cotton seed hulls. No circulation. Pull tbg out of well. Let cement set 24 hrs. Run wireline in to check depth of cement. Found cement @ 1410'. TIH w/tbg to 951'. Est circulation & pump dn tbg 111 sks 60/40 Poz mix w/4% gel. Fill well from top to bottom. Pull tbg out of well. Dig out csg 4' below surface. Cut off csg & weld plate on csg. Back fill & level.

Name of Plugging Contractor: Consolidated Oil Well Services License #: 31440
Address: 1322 S. Grant Chanute, Kansas 66720
Name of Party Responsible for Plugging Fees: Meritage KCM Exploration, LLC
State of Kansas County, Anderson, ss.

Larry Bryant (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry Bryant
(Address) 115 North Oak Garnett, Kansas 66032



SUBSCRIBED and SWORN TO before me this 8th day of July, 2006
My Commission Expires:
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED JUL 17 2006 KCC WICHITA

Handwritten initials/signature in the bottom right corner.