

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: K & N Petroleum
 Address: 513 West 6th Street, Ellinwood, Kansas 67526
 Phone: (620) 564-3422 Operator License #: 3208
 Type of Well: SWD Docket #: D-15,592
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: September 13th, 2004 (Date)
 by: Virgil Clothier (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: 3490' Bottom: N/A T.D. 3506'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-159-20,211-0000
 Lease Name: Ringwald
 Well Number: #1-V *KCC BEN 9-24-04*
 Spot Location (QQQQ): NW - SE - SE
 990' Feet from North / South Section Line
 990' Feet from East / West Section Line
 Sec. 8 Twp. 19 S. R. 10 East West
 County: Rice *6/19*
 Date Well Completed: 3/17/1969 *KCC BEN 9-24-04*
 Plugging Commenced: 9/14/04
 Plugging Completed: 9/20/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	240'	8-5/8"	240'	0'
	Production	0'	3488'	4-1/2"	3488'	1610.43'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Had pit and cellar dug. Spot sand on bottom. Got 40 bbls in hole. Spot 4 sx on bottom. M.I.R.U. jacks. Pulled slips and broke off casing head. Pulled stretch. Trip in hole with knife and cut at 1700' - wouldn't pull. Cut at approximately 1600'; pulled to 1300' - Allied pumped 35 sacks. Pulled to 850' - pumped 35 sacks. Pulled to 300' - pumped enough to circulate to surface. Trip out of hole with rest of pipe - cellar full. Washed up and tore down jacks. Rigged down and moved off.

Name of Plugging Contractor: D. S. & W. Well Servicing, Inc. License #: 6901

Address: P.O. Box 231, Claflin, Kansas 67525

Name of Party Responsible for Plugging Fees: K & N Petroleum

State of Kansas County, Barton, ss.

Edward S. Nemnich

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God

KAREN J. MITCHELL
 Notary Public - State of Kansas
 My Appt Expires 4/13/06

(Signature) *Edward S. Nemnich*

(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 22nd day of September, 20 04

Karen J. Mitchell
 Notary Public

My Commission Expires: 4/13/06

Mail to: **KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202**

**RECEIVED
SEP 23 2004
KCC WICHITA**