

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-031-22226-00-00
Spot: SENWNW Sec/Twnshp/Rge: 13-23S-16E
710 feet from N Section Line, 1240 feet from W Section Line
Lease Name: GRAHAM Well #: 18
County: COFFEY Total Vertical Depth: 710 feet

Operator License No.: 31488
Op Name: GEORGE, MARK
Address: 817 "C" STREET
LEROY, KS 66857

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40	0	

\$ 35.00

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/13/2006 2:00 PM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: NICK BROWN Company: NICK BROWN Phone: (620) 496-6242

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASD 5 5/8" BORE TO 710'. A DRILL BIT WAS LOST IN THE WELL AT THAT DEPTH. NO FURTHER PROGRESS WAS POSSIBLE. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT 700' AND TO CIRCULATE THE BORE FULL OF CEMENT FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: PARTIAL
Date/Time Plugging Completed: 07/13/2006 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE WELL TO 700'. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE 1" PIPE TO 700'. THE 1" PIPE WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED
JUL 24 2006
KCC WICHITA

RECEIVED
KCC DISTRICT #3
JUL 19 2006 CPT
CHANUTE, KS

INVOICED
DATE 7-25-06
2007060242

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

RET