

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01681-00-00
Spot: NENESE Sec/Twnshp/Rge: 6-18S-10W
2326 feet from S Section Line, 425 feet from E Section Line
Lease Name: R SCHLICHT Well #: 1
County: RICE Total Vertical Depth: 3215 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3005		
SURF	12	200		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/08/2006 2:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: Sand perfs to 2900' and cap with 5 sxs cmt; perf @ 1250', 900' & 250'; run tubing to 1250' & pump 50 sxs cmt; pull tubing to 900' & pump 50 sxs cmt; pull tubing to 250' and circ cmt to surf.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/08/2006 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

6/8/2006 -- Sanded perforations to 2850' and capped with 5 sacks of cement. Perforated at 1250', 900', and 250'. Ran tubing to 1250' and pumped 50 sacks of cement. Pulled tubing to 900' and pumped 50 sacks of cement. Pulled tubing to 250' and circulated cement to surface. Made connection on surface casing and pumped 100 sacks of cement pressured to 500 lbs.

6/15/2006 -- Used 35 sacks of cement to top off.

425 sacks of 60/40 posmix with 4% gel

Copeland Cement #25856

Perfs: **RECEIVED
KCC DISTRICT #2
JUN 26 2006
WICHITA, KS**

Remarks: CONTROL #2006-0026-001

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED
JUL 26 2006
KCC WICHITA

M

PGT