

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01682-00-00
Spot: N2NWSE Sec/Twnshp/Rge: 6-18S-10W
2330 feet from S Section Line, 2085 feet from E Section Line
Lease Name: R SCHLICHT Well #: 2
County: RICE Total Vertical Depth: 3235 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3220		
SURF	12	0		Unknown amount

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/09/2006 4:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/12/2006 1:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Ran sandline down hole and encountered obstruction at approximately 300'. Ran tubing down and passed 300' and continued slowly to 550' using power tongs. After digging out around tubing head to flanged surface head, discovered that the 7" casing was rotted off just above flange and probably on down hole. Cut off 7" at top of flange and welded 5.5" collar and casing on top of flange. Screwed 2" pipe on to side of surface casing to circulate up through and back filled cellar.

6/9/2006 -- Pumped 230 sacks of cement with 300 lbs of cotton hulls.

6/12/2006 -- Ran tubing back down hole to 518' and pumped 200 sacks of cement with 300 lbs of cotton hulls. Let set for approximately thirty minutes and pumped another 100 sacks of cement. Let set for two hours and pumped 8 sacks of gel and 50 lbs of cotton hulls with 75 sacks of cement. Circulated cement. Pulled tubing and topped off with 25 sacks of cement. Pumped 30 sacks of cement at 200 lbs. Down surface casing.

6/15/2006 -- Topped off with 35 sacks of cement.

665 sacks of 60/40 posmix with 4% gel

Copeland Cement #C030575

Remarks: CONTROL #2006-0026-002

Plugged through: TBG

RECEIVED
KCC DISTRICT #2
JUN 26 2006
WICHITA, KS

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

RECEIVED
JUL 26 2006
KCC WICHITA

Form CP-2/3

M

PKT