

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01683-00-01
Spot: S2NESE Sec/Twnshp/Rge: 6-18S-10W
1663 feet from S Section Line, 760 feet from E Section Line
Lease Name: SCHLICHT Well #: 3
County: RICE Total Vertical Depth: 3275 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3275		
SURF	10	282		

Well Type: SWD UIC Docket No: D18216.0 Date/Time to Plug: 06/14/2006 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/14/2006 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

6/14/2006 -- MIRU. Attempted to run sand line and bailer downhole and encountered an obstruction at 62'. Attempted to run 2" tubing through, but still could not get through. Pumped 40 bbls water down, but never got over 150 lbs. Was able to run 1" down past the blockage to 3162" and pumped 40 sacks of cement. Pulled out 1" and perforated at 1250', 900', and 335'. Ran 1" back down to 1250' and pumped 50 sacks of cement. Pulled 1" to 900' and pumped 50 sacks of cement. Pull 1" to 335' and circulated cement to surface.

6/15/2006 -- 50 sacks of cement to top off.

60/40 posmix with 4% gel

Copeland #C030576

Remarks: CONTROL # 2006-0026-003

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

RECEIVED
KCC DISTRICT #2
JUN 26 2006
WICHITA, KS

Form CP-2/3

RECEIVED
JUL 26 2006
KCC WICHITA

n

PKT