

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21951-00-00
Spot: SENESE Sec/Twnshp/Rge: 31-18S-14W
1690 feet from S Section Line, 330 feet from E Section Line
Lease Name: JEANETTE GUNN Well #: 1
County: BARTON Total Vertical Depth: 3565 feet

Operator License No.: 5237
Op Name: PLANO PETROLEUM CORPORATION
Address: PO BOX 860247 1101 E. PLANO PKWY.
PLANO, TX 75074

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3564	1622	200 SX
SURF	8.625	857	0	400 SX

\$ 115.80

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/13/2006 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CURTIS KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/13/2006 7:10 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Kelso sanded off bottom to 3175' and topped with 4 sxs cement.
Kelso tried to cut casing at 2050' - 1926' - and 1622'. Could not pull casing.
Called Log Tech - shot casing off at 1622'.
Kelso pulled a 4' sub. Copeland rigged to 4 1/2" casing and pumped 105 sxs 60/40 pozmix with 200# hulls mixed in - displaced to 1650'.
Pulled casing to 875'. Copeland rigged to casing and pumped 200 sxs with 250# hulls mixed in.
Pulled casing to 400'. Copeland rigged to casing and pumped 45 sxs cement to circulate cement to surface.
POOH. Pulled rest of casing - hole standing full of cement.

Perfs:

Top	Bot	Thru	Comments
3366	3367		
3232	3236		

RECEIVED
JUL 18 2006
KCC WICHITA

Remarks: COPELAND CEMENTING & ACID SERVICES-TICKET #C-030632.

Plugged through: CSG

District: 04

Signed _____

Pat Staab
(TECHNICIAN)

INVOICED

DATE 7-21-06
NO. 2007060237

JUL 14 2006

PAT

ANTARES OIL CORPORATION
1546 COLE BLVD #220
GOLDEN, CO 80401

#1 JEANETTE GUNN

31-18-14W
SE NE SE

CONTR H-30 DRILLING INC CTY BARTON

GEOL _____ FIELD ERNA SO EXT (1/4 S)

E 1903 KB CM 6/7/80 CARD ISSUED 7/2/81 IP P 38 BOPD & WTR
LANS 3232-3236

API 15-009-21,951

SMP	TOPS	DEPTH	DATUM
ANH		878	+1025
NO TOPS RELEASED			
RTD		3565	-1662

8-5/8" 857/400sx, 4 1/2" 3564/200sx
NO DSTS REPORTED
MICT - CO, PF 3232-3236, AC 1000 GAL,
POP & P 38 BOPD & WTR, NO OTHER INFO
TO BE RELEASED AT PRESENT - WILL
RELEASE INFO WHEN AVAILABLE

-	+	-	+
-	+	-	+
-	+	-	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS