

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-39939-00-00
Spot: SWNE Sec/Twnshp/Rge: 35-13S-15W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: DILLNER Well #: 1
County: RUSSELL Total Vertical Depth: 3312 feet

Operator License No.: 6622
Op Name: SCHOENBERGER, J.L. DBA JASON OIL
Address: 363 W 12TH STREET PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3305	0	w/unknown sxs cmt
SURF	0	0		

107.64

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/19/2006 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 230 sxs 60/40 pozmix - 10% gel - 500# hulls.
No surface pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/19/2006 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 1600' and 950'.
TIH with tubing to 1800' - mixed and circulated cement with 125 sxs and 500# hulls.
POOH. Swaged onto 5 1/2" and topped with 80 sxs.
S.I.P. 600#.

Perfs:

Top	Bot	Thru	Comments
1600	1600		
950	950		
474	474		

Remarks: QUALITY CEMENTING COMPANY.

Plugged through: TBG

INVOICED
DATE 7-26-06
TEL. NO. 2007060256

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 25 2006

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

JUL 21 2006

FRED J HAYNES

#1 DILLNER

35-13-15W 33
SW NE NE

Contr. _____ RUSSELL Coun _____

E 1881 Comm 11-12-50 Comp. 1-12-51 IP 25 BOPD

Tops	Depth	Datum
LANS	3052	-1171
ARB	3305	-1424
T.D.	3312	-1431

Casing
 12" 580 CORRECTED CARD
 10" 930 1-19-51
 5" 3305
 SWB 75 80/12 HRS

GORHAM POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS