

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-39090-00-01
Spot: SENENE Sec/Twnshp/Rge: 35-13S-15W
4290 feet from S Section Line, 330 feet from E Section Line
Lease Name: DILLNER Well #: 2
County: RUSSELL Total Vertical Depth: 3303 feet

Operator License No.: 6622
Op Name: SCHOENBERGER, J.L. DBA JASON OIL
Address: 363 W 12TH STREET PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3303	0	w/unknown sxs cmt
SURF	8.625	200	0	w/unknown sxs cmt

\$ 107.35

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/18/2006 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JAMES SCHOENBERGER Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-8027

Proposed Plugging Method: Ordered 330 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/18/2006 2:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

RIH with tubing to 1700' - spotted 270 sxs cement with 500# hulls - circulated cement.
Pulled up to 800' with 50 sxs thru tubing.
Pulled tubing - squeezed 20 sxs cement.
Max. P.S.I. 500#. S.I.P. 400#.
Tied onto annulus and pumped 50 sxs cement.
Max. P.S.I. 500#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
1600			
950			
474			

Remarks: QUALITY WELL CEMENTING.

Plugged through: TBG

INVOICE
DATE 7-26-06
2007060256

District: 04

Signed

Marvin Mills

(TECHNICIAN)

110
RECEIVED
KANSAS CORPORATION COMMISSION

JUL 25 2006

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

JUL 21 2006

PET

REPLACEMENT CARD

JASON OIL COMPANY

"OWWO"

35-13-15W

BOX 701

#2 DILLNER-PATTERSON

APP SE NE NE

RUSSELL, KS 67665

CONTR

UNKNOWN

CTY RUSSELL

GEOL

FIELD GORHAM

E 1886 KB

CM 11/18/81

CARD ISSUED

4/15/82

IP P 3 BO & 90 BWPD

ARB 3308-11

	+	+	+
	+	+	+

SMP	TOPS	DEPTH	DATUM
ANH		927	+ 959
TOP		2764	- 878
HEEB		2990	-1104
TOR		3007	-1121
LANS		3045	-1159
ARB		3302	-1416
TD		3310	-1424

OLD INFO: OPERATOR WAS FRED J. HAYNES
 #2 DILLNER, SPD ?, SET 8" 200; 5" 3303
 COMP AS P 25 BOPD 1/6/61
 CONTR: HAYNES DRILLING 4/11-15-60
 MICT - CO, (ARB OH) SWB 4 BO/3HRS, PB
 3100, PF (LKC) 20/3085-90, AC 500, SSO,
 PB 3078, PF (LKC) 20/3069-74, AC1000G
 CO 3310, POP

NEW INFO: RE-ENTERED 11/18/81, WSH DWN
 TO OTD, MICT - CO, PF (ARB) 9/3308-11
 AC 250G (15%), POP, P 3 BO & 90 BWPD
 11/18/81

INFO RELEASED: 4/15/82
 ADDED OWWO INFO

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS