

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20914-00-00
Spot: NENENW Sec/Twnshp/Rge: 26-8S-17W
330 feet from N Section Line, 2310 feet from W Section Line
Lease Name: HRABE Well #: 5-26
County: ROOKS Total Vertical Depth: 3460 feet

Operator License No.: 4472
Op Name: N.F. PRODUCERS, INC.
Address: 940 WADSWORTH -BLVD. 3RD FLOOR
LAKEWOOD, CO 80214

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3460	0	150 SX
SURF	8.625	249	0	140 SX

\$ 112.45

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/18/2006 9:30 AM
Plug Co. License No.: 4472 Plug Co. Name: N.F. PRODUCERS, INC.
Proposal Rcvd. from: BRETT HILDEBRAND Company: N.F. PRODUCERS, INC. Phone: (303) 519-5788

Proposed Plugging Method: Ordered out 275 sxs 60/40 pozmix - 10% gel -1000# hulls.
Holes in casing from 2850' to 650'.
Emergency plug with rig over the hole.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/18/2006 12:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 3085' - mixed and spotted 100 sxs cement with 800# hulls.
Pulled up to 1542' - circulated cement up 4 1/2" casing with 75 sxs and 700# hulls.
POOH. Swaged onto 4 1/2" and pumped 100 sxs circulating up 8 5/8".

Perfs:

Top	Bot	Thru	Comments
3287	3289		
3282	3284		
3223	3227		
3177	3180		
3168	3171		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

INVOICED
DATE 7-26-06
2007060254

District: 04

Signed _____

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 25 2006

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

JUL 24 2006

107

