

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01012-00-01
Spot: NWNWNE Sec/Twnshp/Rge: 20-9S-21W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: KORTAN Well #: 1
County: GRAHAM Total Vertical Depth: 3812 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3805	0	175 SX
SURF	8.625	240	0	175 SX

\$ 123.89

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/20/2006 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (316) 263-3535

Proposed Plugging Method: Ordered 250 sxs Swift Multi-Density Cement with 500# hulls.
Casing leaks.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/20/2006 10:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Murfin RIH with tubing to 1950' - rigged to tubing and pumped 155 sxs SMD with 350# hulls mixed in.
Pulled tubing to 800' - pumped 30 sxs SMD with 50# hulls mixed in to circulate cement to surface.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 15 sxs SMD.
Max. P.S.I. 500#. S.I.P. 500#.
Rigged to 8 5/8" casing - pressured to 450#. S.I.P. 150#.
Slow bleed off on valve.

Perfs:

Top	Bot	Thru	Comments
3805	3812		ARB OPEN HOLE
3582	3585		
3573			
3540	3542		

Remarks: SWIFT SERVICES, INC-TICKET #10434.

Plugged through: TBG

INVOICED
DATE 7-26-06
INVOICE NO. 200706025!

District: 04

Signed [Signature]
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 25 2006

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

JUL 21 2006

[Handwritten initials]

15-065-01,012
 WICHITA, KS 67218
 #1 KORTAN 'OWWO'

CRUDE RECOVERY CORPORATION
 1650 GEORGETOWN #1 KORTAN 'OWWO' 20-9-21W
 WICHITA, KS 67218 NW NW NE
 CONTR GABLE WELL SERVICE CTY GRAHAM
 GEOL _____ FIELD MOREL
 ELV 2297 KB SPD 4/23/85 CARD ISSUED 6/6/85 IP P 25 BO & 225 BWPD
2294 GL ARB OH 3805-3812
 API 15-065-01,012

	•	
+		+
+		+

SMP	Tops	Depth/Datum
HEEB	3460-1163
LANS	3500-1203
ERO ARB	3803-1506
ARB	3804-1507
ORTD	3809-1512
DDTD	3812-1515

OLD INFO: OPERATOR WAS CITIES SERVICE OIL CO., #2 'A' FURY, SPD E 7/1/50, SET 8 5/8 " 240, 5 1/2 " 3805, COMP AS P 2770 BOPD, ARB OH 3805-3812 (CARD ISSUED 7/21/50), CONTR: UNKNOWN
 NO DSTS
 MICT - CO (ARB OH), DD 3812 TD, SWB DWN, GSO, NAT, POP, DRAW DWN TST 2770 BOPD
NEW INFO: FR 4/15/85, RE-ENTERED 4/22/85, WSH DWN TO ORTD, SET 5 1/2 " 3805 / 175SX, MICT - CO, (ARB OH), SWB DWN, GSO, NAT, POP, P 25 BO & 225 BWPD, 5/17/85