

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

API # 15 - 165-21,464-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 3-25-89.

Well Operator: Hembree Energy, LLC KCC License #: 33146
(Owner/Company Name) (Operator's)
Address: 1801 E 56th Ave City: Hutchinson
State: Kansas Zip Code: 67502 Contact Phone: (620) 728 - 1632
Lease: House Well #: 3-36 Sec. 36 Twp. 16 S. R. 20 East West
- SE - NE - NW Spot Location / QQQQ County: Rush

4180 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

3480 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # ENHR Docket # Other:

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 " Set at: 301' Cemented with: 170 Sacks

Production Casing Size: 5 1/2" Set at: 3851' Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: DV Tool @ 1371' - Cemented with 400 sacks to surface

No Perfs or BP's

Elevation: 2105 (G.L. / K.B.) T.D.: 3860' PBTD: _____ Anhydrite Depth: 1335'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Could not drill past 3250' - Casing bad - Pump 50 sx cement & 15 sx gel down tubing @ 3250' - Pull up to 1470' - Circulate cement to surface w/145 sx cement - Pull rest of tubing from hole and top off w/25 sx cement. Dig out braden head and confirm cement did circulate from DV Tool in 1989.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why: _____

Plugging of this Well will be done in accordance with K.A.R. 82-3-118 and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Fred J Hembree
JUL 12 2006 Phone: (620) 728 - 1632

Address: 1801 E 56th Ave City / State: Hutchinson, KS 67502

Plugging Contractor: Mid Kan Well Service, LLC KCC License #: 33695
(Company Name) (Contractor's)

Address: PO Box 326, Russell, KS 67665 Phone: (785) 483 - 4400

Proposed Date and Hour of Plugging (if known?): 5-19-06 3:00 PM

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7-11-06 Authorized Operator / Agent: Fred J Hembree (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Well already plugged - KCC-Dig 7/20/06.