

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

RECEIVED

Form CP-1  
September 2003

WELL PLUGGING APPLICATION

JUL 20 2006

This Form must be Typed  
Form must be Signed  
All blanks must be Filled

Please TYPE Form and File ONE Copy

KCC WICHITA

API # 15 - 097-20108-00-9 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued.

Indicate original spud or completion date 02/13/73

Well Operator: Lee Banks d/b/a Banks Oil Company KCC License #: 5152  
(Owner/Company Name) (Operator's)

Address: 7701 E. Kellogg, Suite 885 City: Wichita

State: Kansas Zip Code: 67207 Contact Phone: (316) 612-1186

Lease: Smith #1 Well #: 1 Sec. 32 Twp. 30 S. R. 18  East  West

NW/4 - SW/4 Spot Location / QQQQ County: Kiowa

1980 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

660 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8 Set at: 540' Cemented with: 150 Sacks

Production Casing Size: 4 1/2 Set at: 5185' Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: 5055-61 Bridgeplug 4602

Elevation: 2183 ( G.L. /  T.D.) TD.: 5190 PBTD: 4602 Anhydrite Depth: 1010'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Attempt to make pump change, found hole or bad  
csg @ approx. 2325' - set BP @ 4602' - packer @ 2137' Squeeze with 150 sacks. Pressure up  
held - attempt to drill out-iron-csg shifted on squeeze - Plugging, pull minimum of 1010'  
4/12 csg spot plug @ 1010'-40 sacks cement 560'-50 sacks 40'-10 sacks 15 sacks gel on side.  
Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Lee Banks or Brain Siroky

Genesis Well Service Phone: (316) 612-1186 / 316-672-5713  
620-770-0621

Address: 7701 E. Kellogg, Suite 885 City / State: \_\_\_\_\_

Plugging Contractor: Siroky Oil Management KCC License #: KLN 2959 33093 8/06  
(Company Name) (Contractor's)

Address: P.O. Box 464 - Pratt, Kansas Phone: (316) 672-5713

Proposed Date and Hour of Plugging (if known?): When Rig is available.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7-17-06 Authorized Operator / Agent: \_\_\_\_\_  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Banks, Lee dba Banks Oil Co  
Suite 885  
7701 E. Kellogg  
Wichita, KS 67207

July 21, 2006

Re: SMITH #1  
API 15-097-20108-00-01  
NWSW 32-30S-18W, 1980 FSL 660 FWL  
KIOWA COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888

Sincerely



David P. Williams  
Production Supervisor