

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 081-20953-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 8/15/1995 (Spud)

Well Operator: Chesapeake Operating, Inc. KCC License #: 32334  
(Owner / Company Name) (Operator's)

Address: P.O. Box 18596 City: Oklahoma City

State: Oklahoma Zip Code: 73154-0496 Contact Phone: (405) 767 - 4078

Lease: MLP Bruno Well #: 2-34 Sec. 34 Twp. 29S S. R. 34  East  West

SW - NE Spot Location / QQQQ County: Haskell

1980 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1980 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8" Set at: 1820' Cemented with: 675 Sacks

Production Casing Size: 4 1/2" Set at: 5542' Cemented with: 285 Sacks

List (ALL) Perforations and Bridgeplug Sets: (perf) 5354' - 5362' & 5385' - 5390'

Elevation: 2972 ( G.L. /  K.B.) T.D.: 5550' PBTD: 5542' Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Spot plugs with tubing using balanced plug method  
25 sx 5300'-5000'; 25 sx 3010'-2710'; 50 sx 1820'-1220'; 50 sx 600'-4'

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Jim Reisch

Phone: (405) 848 - 8000

Address: 6100 N. Western ave. City / State: Oklahoma City/ OK

Plugging Contractor: Allied Cement KCC License #: 99996  
(Company Name) (Contractor's)

Address: \_\_\_\_\_ Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 07/18/06 Authorized Operator / Agent: \_\_\_\_\_  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 20 2006  
CONSERVATION DIVISION  
WICHITA, KS

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Chesapeake Operating, Inc.  
PO Box 18496  
6200 N Western Ave.  
Oklahoma City, OK 73154-0496

July 20, 2006

Re: MLP BRUNO #2-34  
API 15-081-20953-00-00  
SWNE 34-29S-34W, 1980 FNL 1980 FEL  
HASKELL COUNTY, KANSAS

Dear Operator:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely  


David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888