

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

Please TYPE Form and File ONE Copy

15-159-1917-00-01

API # ~~15-207-19444-00-01~~ (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 7/1/24

Well Operator: Southern Star Central Gas Pipeline KCC License #: 33097

Address: 4700 Hwy. 56 P.O. Box 20010 City: Owensboro

State: Kentucky Zip Code: 42304-0010 Contact Phone: (270) 852 - 4490

Lease: Alden Well #: O-13 Sec. 22 Twp. 21 S. R. 9 East West

SW - SW Spot Location / QQQQ County: Rice

395' Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

5093' Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: Gas Storage

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 16" Set at: 49' Cemented with: NA Sacks

Production Casing Size: 7" Set at: 3333' Cemented with: 445 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2439-2447, 2451, 2461-2485, 2617-2622, 2626-2636, 2642-2661

Elevation: 1666' (G.L. / K.B.) T.D.: 3333' PBTD: 2930' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Clean out to plug-back depth. Run 1" tubing and fill hole solid with cement. Pressure up and top off wellhead. Cut casing 4' below surface and weld cap. Reclaim site.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

RECEIVED
JUL 24 2006
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Terry Wall Phone: (580) 363 - 7316

Address: 1600 N. 13 st. City / State: Blackwell, Ok. 74361

Plugging Contractor: Kings Well Service LLC. KCC License #: 33728

Address: P.O. Box 323 Blackwell, Ok. 74631 Phone: (580) 363 - 3912

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7-19-06 Authorized Operator / Agent: D. Mark Rowe SSC 6P
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Southern Star Central Gas Pipeline, Inc.
4700 Highway 56
Owensboro, KY 42301

July 25, 2006

Re: ALDEN #O-13
API 15-159-19171-00-00⁰¹
SWSW 22-21S-9W, 395 FSL 5093 FEL
RICE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be reviewed by the UPGS Section and the KCC District Office listed below for your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000

Sincerely



David P. Williams
Production Supervisor