

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 111-41
LOCATION NW NW NE
SEC. 4 TWP. 7 RGE. 29

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Emigh
Operator G-M-R Oil Co Address 100 E 2nd Wichita, Kans
Field _____ County Sheridan
Total Depth 4488 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 280' circulated with cement - 5 1/2" at ~~4144~~ 4137'
with 7b sax cement - drilled out to 4144' - perforated at
4102'.

Filled with sand to 4090', set 4 sax cement with dump bailer,
pulled 3850' 5 1/2" - mud to 380', set rock and 1b sax cement,
mud to 350', set plug, rock and 10 sax cement to bottom
cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1953
CONSERVATION DIVISION
Wichita, Kansas

Edmond Perry
District Conservation Agent
Date 7-7-53

PLUGGING
FILE SEC 4 T 7 R 29
BOOK PAGE 111 LINE 4