

15-181-20007-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 28 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name G. Ray Carnahan

Complete Address 1700 Wichita, Plaza Wichita, Kansas

Lease Name Rhoads Well No. 1

Location C NE SE Sec. 13 Twp. 7 Rge. (E) (W) 40

County Sherman Total Depth 4450'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & AXX _____

Other well as hereafter indicated _____

Plugging Contractor Murfin Drlg.

Address Wichita, Kansas License No. _____

Operation Completed: Hour 12:30A Day 26 Month 8 Year 1969

The above well was plugged as follows:

RTD 4450' 8 5/8 csg set at 390' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 2075' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 360' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/28/69
INV. NO. 384-W

Signed: Leo F. Massey
Well Plugging Supervisor