

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-141-20,137 ~~15-141-20,137~~ 00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Shields Oil Producers, Inc.

Complete Address Shields Bldg., Russell, Kansas 67665

Lease Name Schneider Well No. 2

Location NE NE SE Sec. 31 Twp. 8 Rge. 15 (East) (West)

County Osborne Total Depth 3640

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Co. Tools and Allied Cementing Co., Inc.

Address _____ License No. _____

Operation Completed: Hour: 4:45 AM Day: 25 Month: June Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows: Elev. 2013-KB Anhydrite 1294-1325'

Hole circulated and Filled with mud. 50 sacks cement pumped through drill pipe at 990'. 40 sacks cement pumped through drill pipe at 300'. Hole Filled with mud to 40'. Plug and 1/2 sack balls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 10 sacks cement. Mousehole cemented with 10 sacks cement.

Cement used: 50/50 Pozmix w/ 2% gel and 3% cc.

Amount of Surface Casing: 858-272-160 sacks Common Quikset

I hereby certify that the above plugging instructions were given as herein stated.

Signed: _____
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Vacation

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 1982

Signed: William J. Tomlin
Conservation Division Agent

INVOICED

DATE 7-1-82

INV. NO. 577-W

CONSERVATION DIVISION
Wichita Kansas

7-1-82