

4-26-82

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1982
Rev. 8-8-82
CONSERVATION DIVISION
Wichita, Kansas

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-141-20,134-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Shields Oil Producers, Inc.

Complete Address Shields Building, Russell, Kansas 67665

Lease Name Schneider Well No. 1

Location NW NW NE Sec. 31 Twp. 8 Rge. 15 (~~East~~) (West)

County Osborne Total Depth 3570'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Co. Tools and Allied Cementing Co., Inc.

Address _____ License No. _____

Operation Completed: Hour: 1:00 AM Day: 22 Month: April Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows: Anhydrite 1233-68' Elev. 1957 KB
Hole circulated and filled with mud. 50 sacks cement pumped
through drill pipe at 930'. 30 sacks cement pumped through drill
pipe at 250'. Hole filled with mud to 40'. Plug and 1/2 sack hulls
pushed to 40' and hole cemented to base of cellar with 10 sacks
cement. Rathole cemented with 10 sacks cement. Mouschole cemented
with 10 sacks cement.

Cement used: 50/50 Pozmix w/2% gel. and 3% c.c.

Amount of Surface Casing: 8 5/8" (258') 160 Sacks Common Quick Set.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: _____
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Too many hours. Unable to get a room at Russell, Ks.

Signed: [Signature]
Conservation Division Agent

INVOICED
DATE 4-28-82
INV. NO. 92-W