

DISTRICT CONSERVATION AGENT'S REPORT

15-163-00271-00-00

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 127-12  
LOCATION SE NW SE  
SEC. 28 TWP. 8 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease \_\_\_\_\_ Stamper \_\_\_\_\_  
Operator Shell Oil Co Address Great Bend, Kans  
Field \_\_\_\_\_ County Rooks  
Total Depth 3539 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1328' circulated with 650 sax cement - 4 1/2" at 3528'  
with 200 sax cement behind. Plugs & Cement to 3492', top  
perf 3394', filled with chat to 3380', set 4 sax cement  
with dump bailer, pulled 2700' 4 1/2", filled with mud to 250',  
set rock and 15 sax cement, filled with mud to 35', set rock  
and 10 sax cement to bottom cellar.

12-21-51

RECEIVED  
STATE CORPORATION COMMISSION

DEC 21 1951

CONSERVATION DIVISION  
Wichita, Kansas

*Eldon J. ...*  
District Conservation Agent

Date 12-19-51

PLUGGING  
FILE SEC 28 T 8 R 17  
BOOK PAGE 127 LINE 18