

RECEIVED  
STATE COMMISSION

KANSAS  
STATE CORPORATION COMMISSION

MAY 25 1959

CONSERVATION DIVISION AGENT'S REPORT

CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-63-00422-00-00

5-25-59

File No. 35-27 County: \_\_\_\_\_ Rooks

Location: SE SE SE Sec. 29 Twp. 8 Rge. 17 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3453

I have this date completed supervision of plugging of:

Lease Name: Stamper Well No. 1

Operator's Full Name: Murfin Drg Co

Complete Address: 617 Union Center Wichita, Kans

Plugging Contractor: Ace Pipe Pulling Co & Sun Cementing Co

Address: Great Bend, Kans License No. 2

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 6PM Day 12 Month 5 Year 59

The above well was plugged as follows:

8 5/8" at 156' circulated with cement - 5 1/2" 3438' with 75 sax cement  
behind - squeezed at 1010' and 825' with 125 sax cement.

PB to 3222', perforated 3208' - filled with sand to 3190', set 4 sax cement  
with dump bailer, pulled 580', 5 1/2" to 500', circulated hole with heavy mud  
through 5 1/2" (Gel), displaced 20 sax cement through 5 1/2" at 500', heavy mud  
to 150', displaced 20 sax cement through 5 1/2" at 150', heavy mud to 35', set  
bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC. 2 T. 8 R. 17 W.  
BOOK PAGE 35 LINE 27