

DISTRICT CONSERVATION AGENT'S REPORT

B

TO:

15-163-00605-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 32-15

LOCATION NE SE SW

SEC. 29 TWP. 8 RGE. 17

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Stamper

Operator Peel-Hardman Address Box 359 Hoisington, Kans

Field _____ County Rooks

Total Depth 3415 Feet.

Plugging Contractor Bert Self Pipe Pulling

Plugging Contractor's License No. 48

Address _____

(Describe briefly the manner in which the well was plugged)

3 5/8" at 187' circulated with cement - 5 1/2" at 3401 with
100 sax cement behind - Baker plugs to 3225' - perforated
at 3204'.

Filled with sand to 3190', set 5 sax cement with dump bailer
pulled 2700' 5 1/2", filled with mud to 180', set rock and 15
sax cement, mud to 35', set rock and 10 sax cement to bottom
cellar.

Edon Peety
District Conservation Agent

Date 5-21-54

RECEIVED
STATE CORPORATION COMMISSION

MAY 25 1954

CONSERVATION DIVISION
Wichita, Kansas

5-25-54

PLUGGING
FILE SEC. 29 T. 8 R. 17 W.
BOOK PAGE 32 LINE 35