

KANSAS

*Y*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-163-20383-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 16 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
8-16-71

Operator's Full Name Black Petroleum, Inc.

Complete Address 445 O. W. Garvey Bldg., Wichita, Kansas

Lease Name Stamper "A" Well No. 5

Location A/ SE SE SW Sec. 29 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3374'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Shields Drlg.

Address Russell, Kansas License No.       

Operation Completed: Hour 4:45 A Day 13 Month 8 Year 1971

The above well was plugged as follows:

RTD 3374' 8 5/8 csg set at 254' cwc Cmt. Mat. 50-50 poz W/4% added gel.  
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 8-18-71  
INV. NO. 4165-W

Signed: [Signature]  
Well Plugging Supervisor