

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1959
~~05-13-1959~~
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-163-00906-00-00

5-13-59

File No. _____ County: Rooks

Location: NE NE SW Sec. 9 Twp. 8 Rge. 18 (E) (W)

Name of Field: _____ Total Depth: 3489

I have this date completed supervision of plugging of:

Lease Name: Peaslee Well No. 1

Operator's Full Name: John O. Farmer

Complete Address: Russell, Kans

Plugging Contractor: same

Address: _____ License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 3PM Day 9 Month 5 Year 59

The above well was plugged as follows:

8 5/8" at 166' circulated with cement.
Circulated hole with heavy mud, set cementing plug at 500', displaced
20 sax cement through drill pipe, heavy mud to 150', set cementing plug
and displaced 20 sax cement through drill pipe, heavy mud to 40', set
cementing plug, 1/2 sack hulls and 10 sax cement to bottom cellar.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 9 T. 8 R. 18W
BOOK PAGE 40 LINE 10