

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: DOWNING-NELSON OIL CO., INC.  
Address: P.O. Box 372 Hays, KS 67601  
Phone: (785)621-2610 Operator License #: 30717  
Type of Well: D & A Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)* *(If SWD or ENHR)*  
The plugging proposal was approved on: 4/23/06 (Date)  
by: Herb Deines (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
None Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-051-25,509-00-00  
Lease Name: FLAX TRUST  
Well Number: 2-30  
Spot Location (QQQQ): C - W/2 - NW - NE  
700 Feet from  North /  South Section Line  
2310 Feet from  East /  West Section Line  
Sec. 30 Twp. 13 S. R. 20W  East  West  
County: Ellis  
Date Well Completed: 4/24/06  
Plugging Commenced: 4:00PM 4/24/06  
Plugging Completed: 8:00PM 4/24/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	221	8 5/8	221.43	None


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug @ 3900' W/25sks 5th Plug @ 40' W/10sks Circulated 1st Plug 15 Minutes W/55Vis Mud  
2nd Plug @ 1670' W/25sks 15sks In Rat Hole Plugs displaced with mud.  
3rd Plug @ 825' W/100sks 10sks In Mouse Hole Total 225sks 60/40Poz 6%Gel W/1/4#CF/sk  
4th Plug @ 275' W/40sks By Allied Cementing Completed @ 8:00PM 4/24/06

Name of Plugging Contractor: Discovery Drilling Co., Inc. License #: 31548  
Address: P.O. Box 763 Hays, KS 67601  
Name of Party Responsible for Plugging Fees: DOWNING-NELSON OIL CO., INC.  
State of KS County, Ellis, ss.

Alan Downing (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Alan Downing  
(Address) PO Box 372, Hays KS 67601  
SUBSCRIBED and SWORN TO before me this 18 day of July, 2006  
Michele L. Meier My Commission Expires: 7/28/09  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
JUL 24 2006  
KCC WICHITA

PKT