

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

JUL 24 2006

KCC WICHITA

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Gore Oil Company
Address: P.O. Box 2757, Wichita, KS 67201-2757
Phone: (316) 263-3535 Operator License #: 5552
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7-11-06 (Date)
by: David P. Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
L-KC Depth to Top: 3554' Bottom: 3802' T.D. 3812'
Arbuckle Depth to Top: 3803' Bottom: 3812' T.D. 3812'

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 065-01012-0001
Lease Name: Kortan
Well Number: 1
Spot Location (QQQQ): NW - NW - NE -
4950 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 20 Twp. 9 S. R. 21 East West
County: Graham
Date Well Completed: 5-17-85
Plugging Commenced: 7-20-06
Plugging Completed: 7-20-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Oil, Water	0'	240'	8 5/8"	240'	0'
Production	Oil, Water	0'	3805'	5 1/2"	3805'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Start pumping cement down tbg @ 1950'. Pumped 20 bbls & got circ to pit w/water. Pumped 155 sx SMD cement & 350 lbs Hulls & circ approx 12 sx cmt to pit. Pull tbg out of hole. Hook up to 8 5/8" csg and pressure to 450 psi. As soon as pumped, kicked in and psi fell to 150. Water started coming out of ground from connection on 8 5/8". Hook up to 5 1/2" csg & pump 15 sx cmt, pressured to 500 psi and held Shut in 5 1/2" csg w/400 psi. Job complete.


Name of Plugging Contractor: Swift Services, Inc. Murfin Drilling Co., Inc License #: 32382-30606
Address: P.O. Box 466, Ness City, KS 67560-0466

Name of Party Responsible for Plugging Fees: Gore Oil Company
State of Kansas County, Sedgwick, ss.

Larry M. Jack (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry M. Jack
(Address) Wichita, KS

SUBSCRIBED and SWORN TO before me this 21st day of July, 20 06
Rebecca K. Crawford My Commission Expires: 3-20-07
Notary Public



KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT