

RECEIVED

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

JUL 24 2006

KCC WICHITA

Form CP-4

December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: _____ (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

3181-3208 Arbuckle Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 053-01717-0000

Lease Name: Buehler H

Well Number: #3

Spot Location (QQQQ): SE - NE - NE -
3977 Feet from North / South Section Line

550 Feet from East / West Section Line

Sec. 33 Twp. 17 S. R. 8 East West

County: Ellsworth

Date Well Completed: 10/39

Plugging Commenced: 6/6/06

Plugging Completed: 6/6/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	211	10 3/4	211	
	Production	Surface	3181	6	3181	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RU and perforate holes @ 1100', 800, 260'. TIH with 2 7/8" open end tbg to 1100'. Rig up Allied to tubing. Mix & pump 50 sx 60/40 Poz, 4% gel. Fluid circ to surface, pull tbg to 800'. Mix & pump 50 sx 60/40 Poz, 4% gel, pull tbg to 260', mix & pump 50 sx 60/40 Poz, 4% gel. Circ. cement to surface in 6" csg., TOH w/tbg., hook up to 10 3/4", pumped 5 sx & press to 600#, top of 6" csg. Job complete at 11:45 am. Witnessed by Virgil Clothier w/KCC.


Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606

Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.

State of Kansas County, Sedgwick, ss.

Susan Sears (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Susan Sears

(Address) 250 N. Water, Suite 300; Wichita, KS 67202

SWORN TO before me this 7th day of July, 20 06

Susan Brady My Commission Expires: 11-4-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

P157