

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 25 2006
CONSERVATION DIVISION
WICHITA, KS

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Pintail Petroleum, LTD
Address: 225 N Market, Suite 300
Phone: (316) 263-2243 Operator License #: 5086
Type of Well: EOR Docket #: E17417.1
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: May 20th, 2005 (Date)
by: Michael Maier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Lansing Depth to Top: 4008 Bottom: 4014 T.D. 4600
Depth to Top: 4148 Bottom: 4158 T.D. 4600
Fort Scott Depth to Top: 4407 Bottom: 4409 T.D. 4600

API Number: 15-135-30079-00-01
Lease Name: Armstrong
Well Number: #1
Spot Location (QQQQ): SW - SW - _____
660 Feet from North / South Section Line
4620 Feet from East / West Section Line
Sec. 7 Twp. 16 S. R. 26 East West
County: Ness
Date Well Completed: 9-9-65
Plugging Commenced: 5-23-05
Plugging Completed: 5-23-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)					
Formation	Content	From	To	Size	Put In	Pulled Out	
		SURFACE	<u>138'</u>	<u>126'</u>	8 5/8"	133'	0
Mississippi	OIL WATER	Prod.	4599'	5 1/2"	4599'	0	

*KCC 7/26/06
PKT
PER CP 43*

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st PLUG PUMP 20 SX CMT @ 1600'. TUBING FISH @ 1675'. 2ND PLUG PERFORATE @ 1250' & PUMP 100 SX CMT.
DISPLACE TO 1000'. WAIT 2 HOURS & PRESSURE TO 1000#. 3RD PLUG PERFORATE @ 800' & PUMP 170 SX CMT.
MAXIMUM PRESSURE 1200#. SHUT IN PRESSURE 400#. PUMP 200 SX CMT DOWN BACKSIDE. MAXIMUM PRESSURE 300#.
SHUT IN PRESSURE 100#.

Name of Plugging Contractor: WHITETAIL CRUDE License #: 31627

Address: P.O. BOX 544, NESS CITY, KS 67560

Name of Party Responsible for Plugging Fees: PINTAIL PETROLEUM, LTD

State of KANSAS County, SEDGWICK, ss.

BETH A. ISERN (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Beth A. Isern

(Address) 225 N MARKET, SUITE 300, WICHITA, KS 67202

SUBSCRIBED and SWORN TO before me this 24 day of JULY, 20 06

Susan Totterbach My Commission Expires: 9/7/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT