

RECEIVED

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

JUL 26 2006

Form CP-4  
December 2003

Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

WELL PLUGGING RECORD

KCC WICHITA

K.A.R. 82-3-117

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

Lease Operator: Blake Production Company, Inc.

Address: 1601 NW Expressway, Suite 1200, Okla. City, OK 73118

Phone: (405) 286-9800 Operator License #: 31763

Type of Well: WAS SWD Docket #: D-7499  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 6-15-06 (Date)

by: DOUG LEWIS (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 127-00190-00-01

Lease Name: MINNIE S. OR MS PIRTLE

Well Number: #2

Spot Location (QQQQ): SW - SE - SE - NW

2020 Feet from  North /  South Section Line

2260 Feet from  East /  West Section Line

Sec. 24 Twp. 15 S. R. 9  East  West

County: MORRIS

Date Well Completed: 01-01-1957

Plugging Commenced: 6-19-06

Plugging Completed: 6-20-06

Kcc 7/27/06  
PKT CP2/3  
Per dist.  
Ftg's edited  
to match  
spot

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

PLEASE SEE ATTACHED FROM GLACIER

Name of Plugging Contractor: GLACIER WELL SERVICE License #: 5721

Address: Rt. 3, Box 146C, Council Grove, KS 66846

Name of Party Responsible for Plugging Fees: BLAKE PRODUCTION COMPANY, INC.

State of OKLAHOMA County, OKLAHOMA, ss.

JANE CUNNINGHAM (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Jae Cough

(Address) 1601 NW EXPRESSWAY, STE. 1200, OKLA. CITY, OK 73118

SUBSCRIBED and SWORN TO before me this 24 day of JULY

[Signature]  
Notary Public

My Commission Expires: 12/5/07



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT

Glacier Well Service

RECEIVED  
JUL 26 2006  
KCC WICHITA

Blake Production  
Plugging M.S. Pirtle #2

SW SE SE NW  
Sec 24 Twp 15S Rng 9E  
Morris County, Kansas

- 1: RIH w/ safety collar and try to screw onto packer (left hand threads). If not, push packer to bottom w/ sandline and tubing (below 2875 ft.). RD

6/14/2006 GWS RI, ass level packer, RD

- 2: MidWest Survey (Steve @ 913-285-3831) will be over Thursday or Friday, set a Bridge Plug @ 2800 ft. and perf 5 1/2" @ 200 ft for cementing between 5 1/2 and 8 5/8" to surface.

6/15/2006 MidWest set plug @ 2800 ft and perf @ 200 ft. Jeff H called KCC #2 for completion on 6/15/06 @ 4:00 AM received plug from Doug Evans

- 3: Using dump bailer, set 5 sx cement ontop of Bridge Plug at 2799 ft.
- 4: RIH w/ tubing to 400 ft, pump (Consolidated 620-583-7664) 15 sx cement plug (HOT), W/ tubing and packer, wait on plug, Check for holes on backside from 180 to surface, if no holes from 200 ft to surface, circ 5 1/2" from 200 ft., if hole, pull packer, RIH w/ open ended tubing to 200 ft, circ cement, pull tubing, cement backside between 5 1/2" and 8 5/8" w/ 1".
- 5: Call KCC #2 and Consolidated before cementing @ (KCC 316-630-4000) 2 days ahead.

Fax 405-286-9799.

RECEIVED  
 JUL 26 2006  
 KCC WICHITA

DRILLERS LOG

Operator- The Carter Oil Company,  
 Lease --- Minnie S Pirtle # 2  
 Location-- 50'S & 50' West Center of SE SE SW Sec. 24-15S-9E Morris County, Kansas.  
 Contractor-- Adkins Drilling Company, Inc. Great Bend, Kansas.

Formation	From	To
Soil and clay	0	15
Lime	15	30
Shale 30	30	47
Lime & Shale	47	146
Lime	146	150
Set 150' of 8 5/8" Surface Pipe and cemented with 75 sacks of cement.		
Cement	125	150
Shale	150	510
Shale & Sand	510	853
Run D. S. T. @ 853'		
Shale & Lime	853	1150
Shale & Shells	1150	1235
Lime & Shale	1235	1325
Shale & Shells	1325	1540
Lime & Shale breaks	1540	1684
Lime (K C)	1684	2144
Shale wth Lime streaks	2144	2300
Shale & Shells	2300	2460
Shale & Lime	2460	2520
Lime & Chert	2520	2580
Lime	2580	2610
Chert	2610	2625
Chert & Lime	2625	2650
Lime	2650	2664
Lime & Shale	2664	2721
Lime	2721	2760
Shale & Shells	2760	2797
Shale	2797	2912
Lime	2912	3025
Lime & Shale	3025	3095
Lime (Viola)	3095	3194

T. D. 3194'

Set 5 1/2" Casing at 3193' and cemented  
w/150 sacks of cement.

STATE OF KANSAS )  
 ) SS.  
 COUNTY OF BARTON )

Jim Adkins, President of Adkins Drilling Company, Inc. deposes and says that the foregoing is a true and correct copy of the Drillers Log on M Pirtle No. 2, to the best of his knowledge and belief.

Jim Adkins

Subscribed and sworn to before me this 24th day of March 1957.

Pauline E. Adkins  
 Notary Public.

My Comm. Expires 2-29-1960.