

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior Inc.
Address: American Warrior Inc.
Phone: (620) 275-2963 Operator License #: 4048
Type of Well: O & G Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7/11/06 (Date)
by: Jerry Stapleton (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing/KC Depth to Top: 4410' Bottom: 24420' T.D. 6053'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 175-20068 -00-01
Lease Name: Stewart OLUWO KCC 7/28/06
Well Number: 1 PET Per CP 2/3
Spot Location (QQQQ): C - NW - NE -
660' Feet from North / South Section Line
1980' Feet from East / West Section Line
Sec. 25 Twp. 32 S. R. 31 East West
County: Seward
Date Well Completed: 7/31/92
Plugging Commenced: 7/12/06
Plugging Completed: 7/12/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing surf	oil and gas	4410	4420	85/8	1587'	0
Pod				51/2	5047'	1600'


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 4200'w/ 3sx cement. Shoot 51/2 casing off at 1600'. Jet services hooked up, Pumped 15sx gel and 80sx cement plug at 1600'
Pulled 27 jts 51/2 casing. Jet hooked up and pumped 50sx plug at 600', pulled casing. Ran 1 jt 51/2 casing. Jet hooked up and pumped 20 sx plug at 40'. Circulated cement to surface.

Name of Plugging Contractor: ~~Southwest well Services~~ Acid Services LLC License #: 32453 ~~4058~~
Address: P.O. Box 399 Garden City Ks. 67846
Name of Party Responsible for Plugging Fees: American Warrior Inc.
State of Kansas County, Finney, ss.

RECEIVED
JUL 27 2006
KCC WICHITA

JODY L. SMITH (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]
(Address) P.O. Box 399 Garden City Kansas 67846

SUBSCRIBED and SWORN TO before me this 18 day of July, 20 06
Erica Kuhlmeier My Commission Expires: 09-12-09
Notary Public

[Handwritten initials]