

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
**Type or Print on this Form**  
Form must be Signed  
All blanks must be Filled

Lease Operator: Berexco, Inc.  
Address: P.O. Box 20380, Wichita, KS 67208  
Phone: (316) 265-3311 Operator License #: 5363  
Type of Well: Other (lost hole) Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: 19 Jul 2006 (Date)  
by: Steve Pfeifer (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 007-22947-00-00  
Lease Name: Davis Ranch  
Well Number: 2-27  
Spot Location (QQQQ): \_\_\_\_\_ - C - E/2 - NE  
1320 Feet from  North /  South Section Line  
660 Feet from  East /  West Section Line  
Sec. 27 Twp. 34 S. R. 36/5  East  West  
County: Barber  
Date Well Completed: 22 April 2006  
Plugging Commenced: 17 Jul 2006  
Plugging Completed: 19 Jul 2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)			
Formation	Content	From	To	Put In	Pulled Out
					none
	<u>Conductor</u>		<u>60' 20"</u>	<u>60'</u>	<u>0</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

24/April/2006: Filled rat hole and mouse hole with 250 sacks common cement.  
19/July/2006: Ran tubing to 290 feet, pumped 240 sacks 60/40 POZ-Mix with 6% gel, 3% calcium chloride through tubing and bit from 290 feet to 20 feet from surface. Topped off hole to surface with 55 sacks 60/40 POZ-Mix.

Name of Plugging Contractor: Berexco Inc. License #: 5363  
Address: P.O. Box 20380, Wichita, KS 67208

Name of Party Responsible for Plugging Fees: Berexco Inc.  
State of KS County, Sedgwick, ss.

Richard R. Smith, Engineering Technician (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Richard R. Smith  
(Address) Berexco Inc. 2020 North Bramblewood, Wichita, KS 67206

and SWORN TO before me this 25<sup>th</sup> day of July, 2006  
Diana E. Plotner My Commission Expires: Aug 10, 2007  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

**RECEIVED**  
**JUL 27 2006**  
**KCC WICHITA**

*Handwritten initials*