

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-22041-00-00
Spot: NWENWSE Sec/Twnshp/Rge: 17-28S-5W
2420 feet from S Section Line, 1880 feet from E Section Line
Lease Name: DEWEY Well #: 2-17
County: KINGMAN Total Vertical Depth: 3950 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 SOUTH MARKET STREET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	264		

\$ 128.38

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/22/2006 5:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: JOHN ARMBRUSTER Company: DUKE DRILLING CO., INC. Phone: _____

Proposed Pumping Method: Pump 25 sxs @ 900'; 35 sxs @ 315'; 25 sxs @ 60' & circ to surf; 15 sxs in rathole & 10 sxs in mousehole.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 06/22/2006 11:00 AM KCC Agent: GREG EVES

Actual Plugging Report:

Pumped 35 sacks of cement through drill pipe at 900'. Pumped 35 sacks of cement at 315'. Pumped 25 sacks of cement at 60' and circulated to surface. Pumped 15 sacks of cement in rathole and 10 sacks of cement in mousehole.
120 sacks of 60/40 posmix with 4% gel
Allied Cement #23767

Perfs: **RECEIVED
KCC DISTRICT #2
JUN 26 2006
WICHITA, KS**

Remarks:

Plugged through: DP

INVOICED
DATE 7-27-06
2007060269

District: 02

Signed Greg Eves
(TECHNICIAN)

**RECEIVED
JUL 26 2006
KCC WICHITA**

m

PGT