

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-115-21348-00-00  
Spot: NWSW Sec/Twnshp/Rge: 17-19S-1E  
1980 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: BOESE Well #: 2-17  
County: MARION Total Vertical Depth: 2931 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N. MARKET, STE 710  
WICHITA, KS 67202

String Size Depth (ft) Pulled (ft) Comment  
SURF 8.625 200

\$ 95.26

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/10/2006 2:00 AM  
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.  
Proposal Rcvd. from: DUKE Company: C & G DRILLING, INC. Phone: (620) 583-5318

Proposed Pumping Method: Pump 35 sxs @ 250'; 25 sxs @ 60'; 15 sxs in rathole and 10 sxs in mousehole.

Plugging Proposal Received By: GREG EVES WitnessType: NONE  
Date/Time Plugging Completed: 06/10/2006 4:30 AM KCC Agent: GREG EVES

RECEIVED  
KCC DISTRICT #2  
JUN 26 2006  
WICHITA, KS

Actual Plugging Report:

Perfs:

Pulled drill pipe to 250' and pumped 35 sacks of cement. Pulled pipe to 60' and circulated 25 sacks of cement to surface. Pumped 15 sacks of cement in rathole and 10 sacks of cement in mousehole.

85 sacks of 60/40 posmix with 4% gel

Consolidated Well #10124

Remarks:

Plugged through: DP

INVOICED  
DATE 7-27-06  
2007060263

District: 02

Signed Greg Eves  
(TECHNICIAN)

RECEIVED  
JUL 26 2006  
KCC WICHITA

*[Handwritten mark]*

PKT