

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-127-00190-00-01
Spot: SWSESENW Sec/Twnshp/Rge: 24-15S-9E
2916 feet from S Section Line, 3133 feet from E Section Line
Lease Name: MS PIRTLE Well #: 2
County: MORRIS Total Vertical Depth: 3194 feet

Operator License No.: 31763
Op Name: BLAKE PRODUCTION CO., INC.
Address: 1601 NW EXPRESSWAY, SUITE1200
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3193		
SURF	8.625	151		

\$ 103.81

Well Type: SWD UIC Docket No: D07499.0 Date/Time to Plug: 06/19/2006 9:00 AM
Plug Co. License No.: 5721 Plug Co. Name: GLACIER PETROLEUM CO., INC.
Proposal Rcvd. from: JEFF HAWES Company: GLACIER PETROLEUM CO., INC. Phone: (620) 342-1148

Proposed Plugging Method: Set bridge plug @ 2850' & cap w/ 5 sxs cmt; perf csg @ 200'; circ from 200' to surf.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 06/19/2006 2:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Set bridge plug at 2797' and capped with 5 sacks of cement. Ran tubing to 352' and pumped 15 sacks of cement. Pulled tubing to 200' and pumped 85 sacks of cement and circulated to surface from 200' where pipe was perforated.

Common cement with 2% gel

Consolidated Well #10173

Perfs:

Top	Bot	Thru	Comments
3000	3011		
2992	3000		
2931	2974		
2918	2926		
2906	2915		

RECEIVED
KCC DISTRICT #2
JUN 26 2006
WICHITA, KS

INVOICED

7-27-06

DATE 7-27-06
2007060264

Remarks:

Plugged through: TBG

District: 02

Signed Greg Eves
(TECHNICIAN)

RECEIVED
JUL 26 2006
KCC WICHITA

M

PCT