

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-02021-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 18-19S-2W
4323 feet from S Section Line, 5154 feet from E Section Line
Lease Name: ENBERG Well #: 2
County: MCPHERSON Total Vertical Depth: 3145 feet

Operator License No.: 31934 •
Op Name: CASEBEER, INC.
Address: 909 N. HIGH DRIVE
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3075		
SURF	10.75	203		

10221

Well Type: SWD UIC Docket No: D06833.0 Date/Time to Plug: 06/19/2006 12:30 PM
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC
Proposal Rcvd. from: MARK CASEBEER Company: CASEBEER, INC. Phone: (620) 241-2612

Proposed Plugging Method: Sand up 50' above perms. Shoot off at 495' and perf at 475'. Circ to surf.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL
Date/Time Plugging Completed: 06/19/2006 2:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Tubing stuck in hole. Shot off at 495'. Pulled out tubing above 495'. Dropped sand through tubing to 550'. Perforated at 475'. Ran tubing to 460' and circulated cement to surface. Pumped down approximately 65 sacks of cement at 175 lbs in surface casing.

230 sacks of 60/40 posmix with 4% gel

Copeland Cement #C030557
Dyna Log Perf #0909

RECEIVED
KCC DISTRICT #2
JUN 26 2006
WICHITA, KS

Remarks:

Plugged through: TBG

INVOICED
DATE 7-27-06
2007060265

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED
JUL 26 2006
KCC WICHITA

(Handwritten mark)

PCT