

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22019-00-02
Spot: NENWNW Sec/Twnshp/Rge: 11-21S-7W
4950 feet from S Section Line, 4290 feet from E Section Line
Lease Name: HAILE Well #: 1-11
County: RICE Total Vertical Depth: 3513 feet

Operator License No.: 33349
Op Name: LUDWICK, JOHN M. DBA JML COMPA
Address: 217 SOUTH 6TH ST.
STERLING, KS 67579

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3513		75 SX
SURF	8.625	211		105 SX

\$ 114.17

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/02/2006 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 06/02/2006 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3310' and capped with 5 sacks of cement. Cut off casing at 2600'.
Pulled to 1050' and pumped 35 sacks of cement. Pulled casing to 600' and pumped 35 sacks of cement. Pulled casing to 270' and circulated cement to surface.

60/40 posmix with 4% gel

Copeland #C030468

Perfs:

Top	Bot	Thru	Comments
3360	3390		

**RECEIVED
KCC DISTRICT #2
JUN 26 2006
WICHITA, KS**

INVOICED

7-27-06

DATE: 2007060271

Remarks:
Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

RECEIVED
JUL 26 2006
KCC WICHITA

Handwritten mark

PKT