

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20027-00-00
Spot: NW Sec/Twnshp/Rge: 8-22S-3W
3858 feet from S Section Line, 4099 feet from E Section Line
Lease Name: NEUFELDT TWIN Well #: 10
County: HARVEY Total Vertical Depth: 3492 feet

Operator License No.: 3942
Op Name: MONROE, ORVILLE DBA BIG "O"
Address: 2820 PASEO DRIVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3485		125 SX
SURF	10.38	293		300 SX
SURF	8.625	573		100 SX

\$ 113.49

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2006 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 793-2134

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
JUN 20 2006

WICHITA, KS

Plugging Proposal Received By: MICHAEL WILSON WitnessType: NONE
Date/Time Plugging Completed: 06/07/2006 10:30 PM KCC Agent: DAVE WERTZ

Actual Plugging Report:

6/6/2006 -- Sanded back to 3427' and capped with 5 sacks of cement. Shot off 5-1/2" at 1501'. Ran tubing to 575' and circulated with 29 bbls of water. Pumped 3 sacks of cotton hulls and 50 sacks of cement. Pulled to 350' and pumped 95 sacks of cement.

6/7/2006 -- Topped off 5-1/2" with 40 sacks of cement down 5' between 13-3/8" and 8-5/8" filled.

60/40 posmix with 4% gel

Allied #23726

Perfs:

Top	Bot	Thru	Comments
3477	3485		

INVOICED

DATE 7-27-06
2007060272

Remarks:

Plugged through: TBG

District: 02

Signed _____

David Wertz
(TECHNICIAN)

RECEIVED
JUL 26 2006
KCC WICHITA

M

ACT