

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-01717-00-00
Spot: SENENE Sec/Twnshp/Rge: 33-17S-8W
3977 feet from S Section Line, 550 feet from E Section Line
Lease Name: BUEHLER H Well #: 3
County: ELLSWORTH Total Vertical Depth: 3221 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6	3181		
SURF	10.75	211		

\$ 104.68

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2006 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: MARK ROBBIN Company: MURFIN DRILLING CO., INC. Phone: (785) 735-4621

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL
Date/Time Plugging Completed: 06/06/2006 11:45 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Used sand pump to attempt to circulate out sulfate scale bridge at approximately 1500'. After considerable effort to get through sulfate bridge, perforated at 1100', 800', and 260'. Ran tubing to 1100' and pumped 50 sacks of cement. Pulled tubing to 800' and pumped 50 sacks of cement. Pulled tubing to 260' and circulated cement to surface.

60/40 posmix with 4% gel

Allied #18500

Perfs:

RECEIVED
KCC DISTRICT #2
JUN 26 2006
WICHITA, KS

Remarks:

Plugged through: TBG

INVOICED
DATE 7-27-06
200.7060274

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

RECEIVED
JUL 26 2006
KCC WICHITA

(Handwritten mark)

PKT