

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24949-00-00
Spot: W2NENW Sec/Twnshp/Rge: 15-17S-14W
650 feet from N Section Line, 1500 feet from W Section Line
Lease Name: LINSNER Well #: 2
County: BARTON Total Vertical Depth: 3505 feet

Operator License No.: 33530
Op Name: REIF OIL & GAS COMPANY LLC
Address: 250 S. CENTER ST.
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	383		

\$ 113.91

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/20/2006 4:40 PM
Plug Co. License No.: 33724 Plug Co. Name: WARREN DRILLING, LLC
Proposal Rcvd. from: MARK DIPMAN Company: REIF OIL & GAS COMPANY LLC Phone: (620) 653-2976

Proposed Plugging Method: Order 155 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER Witness Type: NONE
Date/Time Plugging Completed: 07/21/2006 4:45 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st. Plug at 3450' w/25 sxs.
2nd. Plug at 940' w/25 sxs.
3rd. Plug at 435' w/80 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Perfs:

Remarks: JET CEMENTING.

Plugged through: DP

INVOICED
7-27-06
20070600279

District: 04

1701

Signed

Ed Schumacher

(TECHNICIAN)

JUL 25 2006

RECEIVED
JUL 26 2006
KCC WICHITA

Form CP-2/3

RET