

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20055-00-00
Spot: NWNESE Sec/Twnshp/Rge: 10-31S-3E
2464 feet from S Section Line, 661 feet from E Section Line
Lease Name: MOWDER Well #: 8
County: COWLEY Total Vertical Depth: 3093 feet

Operator License No.: 9576
Op Name: WHITEMAN, RON DBA GEN-DOR OIL C
Address: 8135 281ST RD
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3093		125 sxs cement
SURF	8.625	217		150 sxs cement

\$ 100.52

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2006 8:00 AM
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.
Proposal Rcvd. from: BRENT WHITEMAN Company: WHITEMAN, RON DBA GEN-DOR Phone: (620) 222-7808

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/13/2006 2:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

6/6/2006 -- Sanded back 67' above perforations at 3000'; dump bailed 6 sacks of cement on top. Shot 5-1/2" casing at 656'. POOH with 16 joints of 5-1/2" casing.

6/13/2006 -- RIH with tubing at 360'. Gen-Dor mixed and pumped 200 sacks of 60/40 posmix with 4% gel to surface.

United Cement #6698

Perfs:

RECEIVED
KCC DISTRICT #2
JUL - 5 2006
WICHITA, KS

Remarks:

Plugged through: TBG

INVOICED
7-27-06
2007060281

District: 02

Signed

Duane Krueger

(TECHNICIAN)

RECEIVED
JUL 26 2006
KCC WICHITA

Form CP-2/3

na

PRET